MB-11SPAN-SLAB_Sheet6_BearingsJoints

BEARING SCHEDULE (IRC:83)

Location	Type	Size X (mm)	Size Y (mm)	Load (kN)	Movement	Layers	Qty
A1-ELAST-FIX	ELASTOMERIC_	400	400	1200.0	FIXED		2
P1-P10-ELAST	ELASTOMERIC_	400	450	1800.0	FREE		40
A2-ELAST-FRE	ELASTOMERIC_	400	400	1200.0	FREE		2



EXPANSION JOINT SCHEDULE (IRC SP:55)

Location	Type	Width (mm)	Movement (±mm)	Gap (mm)	Length (m)	Qty
A1-End Singl	SINGLE_MODUL	120	60	30	12.0	1
A2-End Singl	SINGLE_MODUL	120	60	30	12.0	1

BEARING & EXPANSION JOINT NOTES:

1. Bearings shall conform to IRC:83 (Parts I, II, III) as applicable.
2. Elastomeric bearings: shore hardness 60±5, compression set ≤25%.
3. POT bearings: pot pressure ≤35 MPa; PTFE sliding surface Ra≤0.4μm.
4. Strip seal joints: neoprene seal ASTM D2000; anchor steel S355JR HDG.
5. Bearing replacement provision: jacking sockets at each bearing seat.
6. Inspect bearings every 5 years; replace elastomeric pads at 25 years.

MAJOR-BRIDGE-CH8-450
MAJOR BRIDGE ACROSS RIVER PATHERI AT CH 8+450 PMGSY PKG-III

BEARINGS AND EXPANSION JOINTS SCHEDULE			
Consultant:			
Scale: 1:100	Client:		
Designed:	Checked:	Approved:	
DRG: GAD-MB-11SPAN-SLAB-001	Rev: R1	Date:	Sheet 6 / 8

[illegible] — PLAN

entities=167 rendered=167 skipped=0 text-repairs(r/d)=(0/0)