MB-11SPAN-SLAB_Sheet4_Foundation

DESIGN SCOUR RL 230.000

PARAMETER	VALUE	UNIT
Pile Type	BORED_CAST_IN_SITU	
Pile Diameter	1200	mm
Pile Length	18.0	m
Piles per Pier	4	nos
Spacing c/c	2.5	m
Cap Thickness	1500	mm
Pile Cutoff RL	232.0	m
FOS Bearing	3.0	-
Allow. Bearing Cap.	450.0	kPa
Scour Level RL	230.0	m
Scour Depth	3.5	m

MAJOR-BRIDGE-CH8-450
MAJOR BRIDGE ACROSS RIVER PATHERI AT CH 8+450 PMGSY PKG-III

FOUNDATION DETAILS — TYPICAL PIER
Consultant:
Scale: 1:100
Client:
Designed:
Checked:
Approved:
DRG: GAD-MB-11SPAN-SLAB-001
Rev: R1
Date:
Sheet 4 / 7

PILE SCHEDULE

entities=102 rendered=102 skipped=0 text-repairs(r/d)=(0/0)