MB-11SPAN-SLAB_Sheet7_BOQ

Chainage: 0.450 km | Skew: 64 | Total Length: 113.008 m | Overall Width: 11.908 m

Item	Description	Unit	Quantity	Rate (INR)	Amount (INR)	Ref.
1	EARTHWORK — EMBANKMENT (IMPO	CUM	5272.5	TBC		MORTH 306
2	GRANULAR SUB-BASE (GSB) — AP	CUM	206.2	TBC		MORTH 401
3	CONCRETE M35 — PILE FOUNDATI	CUM	408.08	TBC		MORTH 1700
4	CONCRETE M35 — SUBSTRUCTURE	CUM	628.08	TBC		MORTH 1700
5	CONCRETE M40 — SUPERSTRUCTUR	CUM	1153.00	TBC		MORTH 1700
6	REINFORCEMENT STEEL Fe500D —	MT	105.00	TBC		MORTH 1600
7	PRESTRESSING STEEL (STRANDS	MT	0.00	TBC		MORTH 1600
8	FORMWORK — SUPERSTRUCTURE	SQM	4186.8	TBC		MORTH 1700
9	BITUMINOUS CONCRETE (BC) WEA	SQM	629.0	TBC		MORTH 510
10	ELASTOMERIC / POT BEARINGS (	EACH	44	TBC		MORTH 2060
11	EXPANSION JOINTS (STRIP SEAL	RM	23.8	TBC		MORTH 2060
12	APPROACH SLAB M30 (BOTH ENDS	CUM	89.75	TBC		MORTH 1700
13	RIVER TRAINING WORKS (LUMP S	LS	1	TBC		MORTH 2060
14	RAILING / CRASH BARRIER (M.S	RM	240.0	TBC		MORTH 808
15	WATERPROOFING MEMBRANE — DEC	SQM	1360.0	TBC		MORTH 2060
	TOTAL (CIVIL WORKS — BRIDGE)		TBD	TBC		

NOTES:

1. Quantities are preliminary estimates for budget purposes only.
2. Final quantities to be measured as per IS 1200 / MORTH specifications.
3. Rates as per prevailing State PWD / MORTH Schedule of Rates.
4. 15% contingency to be added for unforeseen items.
5. Preliminary estimated cost: To Be Determined (TBD).

ABSTRACT OF ESTIMATED COST — MAJOR BRIDGE CHR.450

MAJOR BRIDGE CHR.450
MAJOR BRIDGE ACROSS RIVER PATHERI AT CH 8+450 PIMGSY PKG-III

ABSTRACT BILL OF QUANTITIES

Consultant

Scale: 1:100	Client:	
Designed:	Checked:	Approved:
DRG: GAD-MB-11SPAN-SLAB-001	Rev: R1	Date:	Sheet 7 / 7

entities=276 rendered=276 skipped=0 text-repairs(r/d)=(0/0)